



ADDENDUM NO. 6

DATE: July 28, 2022

TO: ALL PROSPECTIVE BIDDERS

SUBJECT: BID No. MDAD-CIP-V043A-4

TITLE: Miami International Airport (MIA) Central Terminal Ticket Counters, Conveyors, and K-1 doors for TC 12 through TC 17

This Addendum becomes a part of the subject solicitation.

A. The following is a change to the Bid document.

- a. All references to the bid submittal due date shall mean Tuesday, August 30, 2022 at 2:00 pm EST.
- b. All references to the question submittal deadline shall mean Friday, August 12, 2022 at 12:00 pm EST. Any technical questions already submitted will not be answered and must be resubmitted using the updated Bid Documents.
- c. The following attachments have been added and can be utilized by proposed bidders and subs.
 - MDAD-CIP-V043A-4 Bid Set Specs Volume I of II
 - MDAD-CIP-V043A-4 Bid Set Specs Volume II of II
 - MDAD-CIP-V043A-4 Drawings
 - MDAD-CIP-V043A-4 CCTV Scope Quantities – Pods 1 -3
 - Addendum No 6 Bid Set Specs Changes (all Addendum #5 references in the letter shall mean Addendum #6)

This Addendum is an essential portion of the bid and shall be made a component thereof.

All other information remains the same.

Page 2

Sincerely,

Handwritten signature in black ink, appearing to read "TKW".

Tiondra Wright
Aviation Senior Contracting Officer
Miami-Dade Aviation Department

c: Clerk of the Board

**MDAD-CIP-V043A-4 CCTV
Scope Quantities – Pods 1 -3**

V043A-4 - CCTV SCOPE

Report Total (Direct Cost):

DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
<i>Estimate Rollup Costs</i>				
POD-1 - TC16 & TC17 - CCTV Scope				
Video surveillance cameras, Type C02, Model AXIS P91 Dome Camera Series	1.00	EA		
Video surveillance cameras, Type H02, Model AXIS P3364 Dome Camera Series	5.00	EA		
Ceiling Pendant Mount Bracket, AXIS 5504-641, for Dome Camera	5.00	EA		
Electric metallic tubing, 3/4" diameter	310.00	LF		
EMT couplings, compression, steel, 3/4" diameter, to 15' H	31.00	EA		
EMT boxes connectors, compression, steel, 3/4" diameter, to 15' H	12.00	EA		
Outlet boxes, pressed steel, 4-11/16" square	6.00	EA		
Outlet boxes, pressed steel, covers, blank, 4-11/16" square	6.00	EA		
Conduit hangers, steel, 3/4" diameter, incl bolt & 12" rod	40.00	EA		
Strap, steel, 1 holes, rigid steel conduit, 3/4" diameter	18.00	EA		
Flexible metallic conduit, steel, 3/4" diameter	30.00	LF		
Flexible metallic conduit, steel, connectors, plain, 3/4" diameter	6.00	EA		
Flexible metallic conduit, steel, connectors, plain, 90 Deg., 3/4" diameter	6.00	EA		
Unshielded twisted pair (UTP) cable, solid, plenum, #24, 4 pair, category 6	8.00	CLF		
Unshielded twisted pair (UTP) connector, RJ45, #24, 4 pair, category 6	12.00	EA		
Video surveillance cameras, Testing and Commissioning	6.00	EA		
Video surveillance cameras, Integration and Programming	6.00	EA		
POD-1 - TC16 & TC17 - CCTV Scope	SUBTOTAL	6.00	EA	

V043A-4 - CCTV SCOPE

Report Total (Direct Cost):

DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
<u>Estimate Rollup Costs</u>				
POD-2 - TC14 & TC15 - CCTV Scope				
Video surveillance cameras, Type C02, Model AXIS P91 Dome Camera Series	1.00	EA		
Video surveillance cameras, Type H02, Model AXIS P3364 Dome Camera Series	5.00	EA		
Ceiling Pendant Mount Bracket, AXIS 5504-641, for Dome Camera	5.00	EA		
Electric metallic tubing, 3/4" diameter	310.00	LF		
EMT couplings, compression, steel, 3/4" diameter, to 15' H	31.00	EA		
EMT boxes connectors, compression, steel, 3/4" diameter, to 15' H	12.00	EA		
Outlet boxes, pressed steel, 4-11/16" square	6.00	EA		
Outlet boxes, pressed steel, covers, blank, 4-11/16" square	6.00	EA		
Conduit hangers, steel, 3/4" diameter, incl bolt & 12" rod	40.00	EA		
Strap, steel, 1 holes, rigid steel conduit, 3/4" diameter	18.00	EA		
Flexible metallic conduit, steel, 3/4" diameter	30.00	LF		
Flexible metallic conduit, steel, connectors, plain, 3/4" diameter	6.00	EA		
Flexible metallic conduit, steel, connectors, plain, 90 Deg., 3/4" diameter	6.00	EA		
Unshielded twisted pair (UTP) cable, solid, plenum, #24, 4 pair, category 6	8.00	CLF		
Unshielded twisted pair (UTP) connector, RJ45, #24, 4 pair, category 6	12.00	EA		
Video surveillance cameras, Testing and Commissioning	6.00	EA		
Video surveillance cameras, Integration and Programming	6.00	EA		
POD-2 - TC14 & TC15 - CCTV Scope	SUBTOTAL	6.00	EA	

V043A-4 - CCTV SCOPE

Report Total (Direct Cost):

DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
<u>Estimate Rollup Costs</u>				
POD-3 -TC12 & TC13 - CCTV Scope				
Video surveillance cameras, Type C02, Model AXIS P91 Dome Camera Series	1.00	Ea.		
Video surveillance cameras, Type H02, Model AXIS P3364 Dome Camera Series	5.00	Ea.		
Ceiling Pendant Mount Bracket, AXIS 5504-641, for Dome Camera	5.00	Ea.		
Electric metallic tubing, 3/4" diameter	450.00	L.F.		
EMT couplings, compression, steel, 3/4" diameter, to 15' H	45.00	Ea.		
EMT boxes connectors, compression, steel, 3/4" diameter, to 15' H	12.00	Ea.		
Outlet boxes, pressed steel, 4-11/16" square	6.00	Ea.		
Outlet boxes, pressed steel, covers, blank, 4-11/16" square	6.00	Ea.		
Conduit hangers, steel, 3/4" diameter, incl bolt & 1/2" rod	40.00	Ea.		
Strap, steel, 1 holes, rigid steel conduit, 3/4" diameter	18.00	Ea.		
Flexible metallic conduit, steel, 3/4" diameter	30.00	L.F.		
Flexible metallic conduit, steel, connectors, plain, 3/4" diameter	6.00	Ea.		
Flexible metallic conduit, steel, connectors, plain, 90 Deg., 3/4" diameter	6.00	Ea.		
Unshielded twisted pair (UTP) cable, solid, plenum, #24, 4 pair, category 6	30.00	C.L.F.		
Unshielded twisted pair (UTP) connector, RJ45, #24, 4 pair, category 6	12.00	Ea.		
Video surveillance cameras, Testing and Commissioning	6.00	Ea.		
Video surveillance cameras, Integration and Programming	6.00	Ea.		
Pull boxes, steel, type SC, 18" W x 18" H x 8" D, NEMA 1	1.00	Ea.		
Knockouts, metal boxes & enclosures, with hole saw, 3/4" pipe size, to 8' high	6.00	Ea.		
Knockouts, metal boxes & enclosures, with hole saw, 2" pipe size, to 8' high	1.00	Ea.		
Electric metallic tubing, 2" diameter	10.00	L.F.		
Hangers, trapeze channel support, steel, 12" wide, steel, 12 Ga	2.00	Ea.		
Strap, steel channel, EMT, 2" diameter	2.00	Ea.		
EMT couplings, compression, steel, 2" diameter, to 15' H	1.00	Ea.		
EMT boxes connectors, compression, steel, 2" diameter, to 15' H	2.00	Ea.		
Rigid galvanized steel conduit, 2" diameter, to 10' high, includes 11 couplings per 100'	10.00	L.F.		
Conduit fittings for rigid galvanized steel, bushings, plastic, 2" diameter	2.00	Ea.		
Rigid galvanized steel conduit couplings, 2" diameter, to 10 high	1.00	Ea.		
Concrete core drilling, core, reinforced concrete slab, 3" diameter, up to 6" thick slab, includes bit cost, layout and set up time	1.00	Ea.		
Firestopping, metallic piping, non insulated, through floors, 3" dia	1.00	Ea.		
POD-3 -TC12 & TC13 - CCTV Scope	SUBTOTAL	6.00	EA	

Addendum No. 6 Bid Set Specs Changes

July 18th, 2022

Ms. Mel Blanco, Construction Manager III, R.I.D.
Miami-Dade Aviation Department
Miami International Airport
Building 3030, 2nd Floor
Miami, FL 33159

Re: Miami International Airport
V043A-4 MIA Central Terminal Ticket Counters TC 12 through TC 17
MIA Contract A16-MDAD-03
BA Project No. 19001.000
Addendum #5

Dear Mel;


The following changes were incorporated into Addendum #5 of the Bidding documents for the above referenced project:

- Architectural Drawings A-CP01, A-CP02, and A-CP03 were revised to hide the locations of the Security Cameras and the Blue Lights. The Sensitive Security Information (SSI) note was removed. Addendum #5 and the date 07/18/2022 was added to the titleblock.
- Architectural Drawing GN-01 Index of Drawings was revised to add a column to the index for Addendum #5 dated 07/18/2022. Addendum #5 and the date 07/18/2022 was added to the titleblock.
- Electrical Drawings E-PP01, E-PP02, and E-PP03 were revised to hide the locations of the Security Cameras and the SSI note was removed. Addendum #5 and the date 07/18/2022 was added to the titleblock.
- Low Voltage drawing TT1.301 Level 3 – Telecom Overall Plan is a new drawing added to the set.
- Low Voltage drawing TT4.301 Existing Telecom Rm G3325 (Level 3) is a new drawing added to the set.
- Low Voltage drawings TT2.201, TT2.202, TT2.203 were revised to hide the locations of the Security Cameras and scope narrative was added. The SSI note was removed. Addendum #5 and the date 07/18/2022 was added to the titleblock.
- Low Voltage drawings TT4.201 and TT4.202 were revised to add ASN Rack Scope and the SSI note was removed. Addendum #5 and the date 07/18/2022 was added to the titleblock.
- Low Voltage drawing TT6.001 was revised to hide the location of the Security Cameras and the SSI note was removed. Addendum #5 and the date 07/18/2022 was added to the titleblock.

- Low Voltage drawing TT6.002 was revised to change the Fiber Network Requirements and the SSI note was removed. Addendum #5 and the date 07/18/2022 was added to the titleblock.
- Low Voltage drawing TT8.001 was revised to hide the location of the Security Cameras and the SSI note was removed. Addendum #5 and the date 07/18/2022 was added to the titleblock.
- Revision to all other drawings not listed above was limited to the removal of the SSI note only.
- The Project Specifications were revised to remove the SSI note from the cover page.

Sincerely,

Bermello, Ajamil & Partners, Inc.



Sergio Pendas, AIA
Project Manager

cc: B&A Project File No. 19001.000